BID OPENING CERTIFICATION RECORD Address PBE Amount 1805 KENNESAW **PUBLIC BODY ESTIMATE: PUBLIC BODY ESTIMATE: PUBLIC BODY ESTIMATE: PUBLIC BODY ESTIMATE:** PUBLIC BODY ESTIMATE: **ATTENDEES BIDDERS** Address: This is to certify that bids for the job identified above were publicly opened and read aloud in the Neighborhood & Business Services Office located at 600 E. Trade Street, Charlotte, NC Bids Opened By Mandal OOO Bids Recorded By: Much Juglor Witnessed By: _____ Date: Responsive bids are those which fall within a range of 15% above and 15% below the public body cost estimate. As a Note: general rule, the lowest responsive bid is recommended to the property owner for consideration.



weeks

JORANA.

Addl

TLC by CLT

CITY OF CHARLOTTE

HOUSING & NEIGHBORHOOD SERVICES

Company Acknowledgement:

The undersigned, having become thoroughly familiar with the terms, conditions, limitations, and provisions of the housing improvement work to be performed at 1805 Kennesaw Dr be funded advised respective contractual, for the sum of money:

through the City of Charlotte Housing & Neighborhood Services, in addition, having fully inspected the site in all particulars, hereby proposes and agrees to fully perform the work within the time stated and in strict accordance with the proposed contract documents including furnishing of any and all labor and materials, and to do all work required to complete said Work in accordance with the All labor, materials, services and equipment necessary for the completion of the Work shown on the Drawings and in the Specifications: Thirty seven thousand seven hundred & 2100 Dollars (\$ 37,780-) Written total Number of Pages: Specs Dated: Addenda # 1 Dated: Number of Pages: 10 Addenda # 2 Dated: Number of Pages: Project Schedule: Minimum Start Date - upon issuance of NTP TART DATE: Completion Deadline: (please provide projected completion date with bid submission) 12.28-18 Shart date Please Print and Sign: Company Name/Firm: Authorized Representative Name: Date: Signature:

A881



TLC by CLT

CITY OF CHARLOTTE

HOUSING & NEIGHBORHOOD SERVICES

Requirements For Bidders

The City awards rehabilitation bids to the lowest responsive and responsible bidder. A responsible bidder for the safe home program is one who:

- 1) Is a licensed general contractor in the State of North Carolina;
- 2) Has an Renovate, Repair & Paint Certification (http://www2.epa.gov/lead/renovation-repair-and-painting-program);
- 3) Is not listed on a local, state or federal debarment list;
- 4) Carries an appropriate amounts of insurance;
- 5) Can provide references verifying the contractor has completed work of a similar scope in a good workmanship like manner or successfully completed prior work for the Safe Home program. Referenced work must have been completed in one year or less from date of this invitation to bid.

A responsive bidder must:

- 1) Submit all requested documentation on time;
- 2) Meet the above requirements for responsibility at the time of bid submittal;
- 3) Have the capacity to meet the required schedule for the project.
- 4) Existing rehab projects contracted by the contractor must be on schedule.

The City reserves the right to waive any minor informalities or irregularities, which do not go to the heart of the bid submittal or prejudice other offers, or to reject, for good and compelling reasons, any or all bid submittals.

Elizabeth Lamy Santos
Rehabilitation Specialist
City of Charlotte
Housing and Neighborhood Services
600 E. Trade St.
Charlotte, NC 29202

PH: (704) 336-3333 Cell: (704) 620-9090

HOUSING & NEIGHBORHOOD SERVICES

http://housing.charlottenc.gov | 600 E. Trade Street | Charlotte, NC

A001

Work Specification

Prepared By: City of Charlotte Housing & Neighborhood Services 600 E. Trade Street Charlotte, NC 28202 (704) 336-7600

	Property Details	gram and an area of the second and t	•		,	
	Address:	1805 Kennesaw Dr		Owner:	Peggy Covingtor	1
		Charlotte, NC 28216		Owner Phone:	Home: (704) 817	'-9919
	Structure Type;	Single Unit		Program(s):	Healthy Homes	
	Square Feet:	696			Tested- NO LEA Targeted FY19 (
	Year Built:	1964			raigetea i i i a (obbo)
	Property Value:	42500				
	Tax Parcel:	07506343				
	Census Tract:					
	Property Zone:	Council District 2				
	Fiberglass Bathtub a	nd Shower Surround			BATHRO	OM - MAIN
,	Install a 5' white Swan handled tub/shower div	or equivalent 3-plece, fiberglass bathtu verter valve and drain.	ub and surrou	ınd, Caulk all se	ams and penetrat	lons. Include new single
		T_{8}	Bid Cost		x /	= 2300
			2.2.2.	Base	Quantity	Total Cost
2	Prep & Paint Room S	emi Gloss			BATHRO	OM - MAIN
	fungus, dirt, and dust for with owner's choice of	ware and accessories not to be painted rom surfaces, Fill holes and cracks, Pri low VOC acrylic SEMI-GLOSS latex, F accessories, Any moving of furniture re	me all new n Painting shall	naterials and spo include walls ar	ot prime existing w	ith acrylic latex. Top coat

Bld Cost: _

Base

Quantity

Add 1

Work Specification

31	Wallpaper Removal				BATHRO	OOM -	MAIN
=	Remove existing wallpaper to a clean wall surface ready for procompound sanded and smoothed if needed,	rimer and paint.	Include a t	thin ski	m coating of	lightw	velght joint
		Bid Cost:	-	х	(=	175-
			Base		Quantity		Total Cost
4	Vanity/ Counter Top/ Sink				BATHRO	OM -	MAIN
	Install new vanity cabinet complete with counter top of laminat single handled metal faucet with drain and pop-up , P- trap, su	e with vitreous o pply lines, full p	china sink o ort ball typ	or mark e shut-	ole-lite top wi off valves &	th pre escute	formed sink. Include cheon plates.
		Bld Cost:	**************************************	х	(=	500-
			Base		Quantity		Total Cost
8	Bath Mirror				BATHRO	OM -	MAIN
	Install mirror sized at the width of vanity by 36" high. Use adhe	sive manufactu	red for this	purpos	se and apply	to so	und backing.
		Bid Cost:	\	X	1	=	225
			Base		Quantity		Total Cost
1.	GFCI Receptacle 20 AMP			- •	BATHRO	OM -	MAIN
y)	Install a flush mounted, ground fault circuit interrupted, duplex	receptacle and	cover plate	e. Fish			
				V	1		200-
		Bid Cost:	Base	X	Quantity		Total Cost
\sim					·		
D	Light Fixture Replace			ED H.J	BATHRO		
	Replace or install a celling mounted 2 bulb or wall mounted 4 b	oulb strip, UL ap	proved, L	ED lign	it fixture with	snad	e and lamps.
		Bid Cost:		x_		_=_	150
			Base		Quantity		Total Cost
					-,		10tai 003t

	Work openication						
8	Resilient Flooring				BATHRO	oom -	MAIN
٧	Install 25 year warrantled resilient floor covering per manufacture quarter-round at all perimeters to complete installation.	rer's specifica	tions. Includ	le trans	sitions and p	alnted	or stained wood
	•	Bid Cost:	-	Х		_=	275
			Base		Quantity		Total Cost
(a)	Commode Replace 1.6 GPF				BATHRO	OOM -	MAIN
JV.	Install a new commode shall be complete with seat, seal, supp type, free-standing close-coupled closet combination, vitreous a 1.6 gallon water-saver as required by the North Carolina Stat Mansfield, or Kohler brands. Color shall be white.	china compiyir	ng with U.S.	Comn	nercial Stand	lard C	320-63, and shall b
		Bid Cost:		X	1	=	350-
		Bid Cost	Base	^`	Quantity		Total Cost
\widehat{n}	Grab Bars				BATHRO	OOM -	MAIN
19	Install 1 1/2" diameter S/S Grab Bars on 3 walls at height of 36 Owners choice of locations.	" (include woo	d blocking i	n wall.	Each bar mu	ust hol	d 300 pounds).
		Bld Cost:		Х	**	=	300-
		D/a 0001	Base		Quantity		Total Cost
	Accessory Set - 3 Piece Chrome				BATHRO	oom -	MAIN
الأك	Install a chrome plated steel bathroom accessory set consisting	g of a 24" towe	el bar, hand	towel i	ing, and toll	et pap	er holder,
		Bld Cost:	Control of the Contro	Х	(=	175
		Bla Cost	Base	^_	Quantity		Total Cost
	Resillent Flooring - Vinyl Plank		•		BEDRO	МС	
12)	Install 25 year warrantled resilient plank floor covering per mar wood quarter-round at all perimeters to complete installation.	ufacturer's sp	ecifications.	Includ			ainted or stained
		Bid Cost: _	·	×	(=	750
		Bid Cost: _	Base		Quantity	P	Total Cost

	Work Specification							
13)	Ceiling Repair and Repaint				BEDRO	ОМ		
נעי	Repair ceiling finish. Patch drywall or plaster holes in ceil mesh with the appropriate material. Wet sand and smootl	ing greater than one h. Re-paint entire cel	inch. All ot ling white.	hers u	se an adhes	ilve me	esh and mud over	
	Sandra de la Colonia de la Col	Bid Cost:		x_	(=	150-	
			Base		Quantity		Total Cost	
^								
(14)	Resilient Flooring - Vinyl Plank				BEDRO	OM 2		
<u> </u>	Install 25 year warrantied resilient plank floor covering pe wood quarter-round at all perimeters to complete installat		cifications.	Includ	e transitions	and p	painted or stained	
		Bid Cost:	-	Х	(=	775	
		<u></u>	Base		Quantity		Total Cost	
10	Re-secure Door Hinge		••		BEDRO	OM 2		
	Re-secure or replace if necessary lower hinge for bedroom door where it has come loose from the door frame.							
		Bld Cost:		_x_	- Landerson		100-	
			Base		Quantity		Total Cost	
6	Wrought Porch Frame Columns - Front Porch				EXTERI	or	Exterior	
	Remove and replace existing wrought iron support colum	ns with new wrought	Iron suppo	rt colu	mns of simi	ar styl	e, black in color.	
		Bld Cost:		_x_		_=_	550	
			Base		Quantity		Total Cost	

	Work Specification								
17)	Install Handrails and Guards - Front Porch		•		EXTERIO)R	Exteri	or	
	Remove existing handrail for the stairs, and install Code-approguards around the perimeter of the front porch. All railings and	ved handrails I guards shall I	on both side se wrought i	s of the	e stairs, as v ack in color.	vell a	s Code-approved		
		Bid Cost: _	-	_x_		_=_	900-		
			Base		Quantity		Total Cost		
18	Gas Pack				EXTERIO)R	Exteri	or	
	Install combination AC/furnace unit, minimum 14 SEER design per manual J and Manual D for this home.								
		Bld Cost:	-	Х	- Barrell Control	=	6,000-		
			Base		Quantity		Total Cost		
(19)	Tear Off & Reroof Shingles				EXTERIO)R	Exteri	or	
	Remove and dispose of existing roofing, inspect and repair roof 30 year architectural shingles. Include ice and water shield at a necessary accessories.	of deck (include all roof edges,	e 96 sq.ft. of felt paper, s	deckir hingle	ig replacem over ridge v	ent In ent, b	bid) and install ne coots, flashing and	w all	
		Bid Cost: _	Magazine granum and an and an	_x_	(_=_	4200 -		
			Base	.,	Quantity		Total Cost		
(20)	Crawl Space Access Door				EXTERIO)R	Exteri	or	
	Install a 3/4" pressure treated plywood access door in a 2" x 4"	' pressure trea	ted frame.	Provide	galvanized	iron !	hinges and hasp.		

Total Cost

Quantity

	Work Specification				٠			
91)	Wooden Porch Frame Column - Rear Stoop				EXTERIO)R	Exte	erior
	Install an additional wooden support column to support rear sto	oop overhang.	Paint to ma	itch ex	isting.			
		Bid Cost:		_x_	-10	=	350-	
			Base		Quantity		Total Cost	:
22	Cleaning Exterior Brick				EXTERIO)R	Exte	erior
	Clean moss, algae, salt crystals, and any other soil from exterions af e brick/masonry cleaner applied with a natural or synthetic between the control of th	or brick surface pristle brush. D	s of the hor o not use a	me by wire b	using an app orush.	oropria	ite environment	tally-
		Bid Cost:	-	_x_	and the same of th	_=_	650-	
			Base		Quantity		Total Cost	
23)	Electric Service 200 AMP				GENERA	L RE	QUIREMENTS	
	Replace electrical service with new 200 amp, main disconnect, service cable, ground rods and cable. Include replacement of	110/220 volt, 2 all sub-panels.	24 circuit pa Caulk exte	nel bo lor ser	ard, meter s vice penetra	ocket, ıtlon.	weather head,	
		Bid Cost:		x	(_=_	2500	
			Base		Quantity		Total Cost	
24)	Combination CO / Smoke Detector Hard Wired				GENERA	AL RE	QUIREMENTS	
- Aller	Install a hard wired combination carbon monoxide and smoke of	detector with ba	ittery back	up.				
		Bid Cost:	***************************************	Х	-	=	900-	
			Base		Quantity		Total Cost	
25)	Smoke Detector Hard Wired				GENERA	AL RE	QUIREMENTS	
	Install UL approved, interconnected, ceiling mounted smoke are battery backups in bedrooms and outside of sleeping areas. ***Price is for (2) detectors.	nd heat detecto	rs permane	ntly wi	red into a re	ceptad	ele boxes with	

Bid Cost: _

Base

Quantity

	Work Specification							
(2/0)	Portable Toilet				GENER	AL RE	QUIREMENTS	
(All)	Provide temporary toilet facilities from job start until approva	l of permanent fa	cilities.					
		Bid Cost:		X		=	300-	
			Base		Quantity		Total Cost	
	Permits Required				GENER	AL RE	QUIREMENTS	
20	The contractor is responsible obtaining and paying for all pe	rmits required. Sa	aid permits s	shall in	clude all ite	ms in (this scope of work.	
		mi-1 04.		· v		=	500	
		Bid Cost:	Base	_^_	Quantity		Total Cost	
(0)	Dumpster				GENER	AL RE	QUIREMENTS	
(28)	After procuring all required permits, place AS MANY roll-off	dumpatara an nac	ded without	dama				
	debris using dust control methods. Remove dumpster and reaway daily using dump trailers.	epair any evidenc	e of the dun	npster	s use. Cont	ractor i	may haul debris	
		Bld Cost:	-	х	1	=	500	
		DIG 00011	Base		Quantity		Total Cost	
(00)	House Number				GENER	AL RE	QUIREMENTS	
20	Install brass, aluminum, or iron house numbers with nails. Numbers must be 4 inches tall with a stroke-width of 1/2 inch per Code. Numbers are not permitted to be plastic or stickers.							
		Bld Cost:		X		=	100	
		Bid 003	Base		Quantity		Total Cost	
	Resilient Flooring - Vinyl Plank				HALL		•	
(39)	Install 25 year warrantled resilient plank floor covering per m wood quarter-round at all perimeters to complete installation		ecifications.	Includ		s and p	painted or stained	
		Bid Cost:		_x_	./	=	350-	

Base

Quantity

	Work opecinication				
(21)	Prep & Paint Ceiling			HALL	
رير <u>د</u>	Remove or cover hardware and accessories not to be painte fungus, dirt, and dust from surfaces. Fill holes and cracks. Pr with Owner's choice of low VOC acrylic flat latex in all habital Replace or uncover hardware, fixtures and accessories. Any	lme all new mate ole rooms and lo	orials and spot w VOC acrylic	t prime existing with a s semi-gloss latex in ki	crylic latex, Top coa
		Bld Cost:		x	250
			Base	Quantity	Total Cost
50	Resilient Flooring - Vinyl Plank			KITCHEN	
30	install 25 year warrantied resilient plank floor covering per moved quarter-round at all perimeters to complete installation.		cifications. In	clude transitions and p	painted or stained
		Bld Cost:	- Charles	x (=	650
			Base	Quantity	Total Cost
33	Floor System Repair			KITCHEN	
	Remove all fixtures not built in. Dispose of damaged/unsafe joists hung 16" on center, plywood or tongue and groove subcode. ***This work is to include the area transitioning from the kitch item is to cover ALL floor system repair in the kitchen/dining also if any damage is present after the removal of kitchen ba	floor. Include rep en to the hallway area - where the	olacing all dete	eriorated band joists a ryer is currently locate	nd insulating floor to

Bid Cost: _

Base

Quantity

9/28/2018

ASS 1

Work Specification




Wallpaper Removal

KITCHEN

Remove existing wallpaper to a clean wall surface ready for primer and paint. Include a thin skim coating of lightweight joint compound sanded and smoothed if needed.

***Price include removal of ALL wallpaper in kitchen AND dining room areas. All wallpaper with the fruit motif is to be removed.



Bid Cost: _	X	=	200
	Base	Quantity	Total Cost



KITCHEN

Remove or cover hardware and accessories not to be painted. Scrape loose, peeling, cracked and blistered areas. Clean oil, grease, fungus, dirt, and dust from surfaces. Fill holes and cracks. Prime all new materials and spot prime existing with acrylic latex. Top coat with owner's choice of low VOC acrylic SEMI-GLOSS latex. Painting shall include walls and any associated trim. Replace or uncover hardware, fixtures and accessories. Any moving of furniture required shall be included.

***Price to include painting dining room area as well, or everywhere where fruit motif wallpaper was removed.


Bld Cost:	•	x	(:	=	400-	
	Base	Qı	uantity		Total Cost	

76) Prep & Paint Ceiling

KITCHEN

Remove or cover hardware and accessories not to be painted. Scrape loose, peeling, cracked, and blistered areas. Clean oil, grease, fungus, dirt, and dust from surfaces. Fill holes and cracks. Prime all new materials and spot prime existing with acrylic latex. Top coat with Owner's choice of low VOC acrylic flat latex in all habitable rooms and low VOC acrylic semi-gloss latex in kitchen and baths. Replace or uncover hardware, fixtures and accessories. Any moving of furniture required shall be included.

***Price is to include painting ceiling over dining area as well.



Bid Cost:	-	X	l	=	100-	
	Base		Quantity		Total Cost	




Cabinets Wall

KITCHEN

Replace wall cabinets. Cabinets are to be constructed of solid maple and plywood. No particle board allowed. See contractor's manual guidelines & specifications for full requirements.

***Price to include turning the corner with the cabinets until you reach the exit door frame. Also include in your price, a cabinet to house the vented range hood. This will be a separate cabinet above the range, located along the right wall of the kitchen.

ALTERNATE: Provide an additional price for the same linear feet of cabinets as above, minus the separate cabinet to house the range hood. With this scenario, the range hood will be housed in the cabinets along the left side of the kitchen.



Bid Cost: X = 1800 Total Cost



Cabinets Base

KITCHEN

Replace base cabinets. Cabinets to be constructed of solid maple and plywood. No particle board allowed. See contractor's manual guidelines & specifications for full requirements.

***Price to include turning the corner with the cabinets and running them to the rear exit door frame. The range is to be relocated, so this run of cabinets will house the kitchen sink only.

ALTERNATE: Provide an additional price for base cabinets that will include a space for the range. With this scenario, the base cabinets will house the range and kitchen sink.





Bld Cost:	-	x(:	= <i>1800</i> ⁻
	Base	Quantity	Total Cost



Counter Tops Replace

KITCHEN

Screw to base cabinet a square edged plastic laminate counter top. Provide end-caps and cutout for sink. Caulk counter top to adjoining walls with low VOC caulking to match wall color. Owner's choice of in-stock color and texture,

***Price to include turning the corner with the counter top and running it to the rear exit door frame. The range is to be relocated, so this run of counter top will house the kitchen sink only.

ALTERNATE: Provide an additional price for a counter top that will include a space for the range. With this scenario, the counter top will have space for the range and kitchen sink.



Bld Cost:	X	<u> </u>	800-
	Rasa	Ougatity	Total Cost


(40)

Double Bowl Sink Complete

KITCHEN

Install a 18 gauge 33" x 22" x 8" double bowl, stainless steel, self rimming kitchen sink including a single handle metal body faucet, rated at 2.0 GPM or less, with a 15 year drip- free warranty, P-trap, supply lines, full port ball type shut-off valves & escutcheon plates on all supply & drain lines. No copper compression fittings.

ALTERNATE: Provide an additional price for a new double bowl sink, including all costs associated with relocating the plumbing from original sink location, to the rear wall of the kitchen.






Bid Cost:	x		650-
	Base	Quantity	Total Cost



Range Hood Exterior Vented - New Installation

KITCHEN

Install an exterior ducted enameled range hood with integral controls and light capable of 100 cfm at 70 sones. Attach hood to cabinet with screws. Include metal vent and roof or wall cap/damper assembly, using #14 copper Romex. Owner's choice of color.



Bld Cost:	X		550
	Base	Quantity	Total Cost

ASS

	Work Specification						
4/2	GFCI Receptacle 20 AMP				KITCHE	N	
	install a flush mounted, ground fault circuit interrupted, duple ***Price is for (2) outlets.	x receptacle and	l cover plat	te. Fish	wire and rep	oair ali	l tear out as needed
	•	Bld Cost:	. British and the state of the	х	(ш	1000
			Base		Quantity	-	Total Cost
142	Exterior Door Weatherstripping Install - Kitchen Exit Doo	r			KITCHE	N .	
	Install rigid aluminum strip with neoprene-type weatherstrippi		ened to sid	es and	head Jams.		
		Bid Cost: _	-	x_		=_	100-
			Base		Quantity		Total Cost
44)	Door Hardware Exterior - Kitchen Exit Door				KITCHE	N	
مرابات	Replace entry hardware. Install mortised dead bolt and lever	handled door, ke	eyed alike,				
l					j		0.0
		Bid Cost:	Base	x_	Quantity	_=_	<i>200</i> Total Cost
45)	Dryer Vent				KITCHE	١	
	Install 4" rigid aluminum vent tubing from the specified dryer land NO screening. Fasteners shall not protrude into the interior aluminum foll tape, not duct tape. Secure duct and hood to ***This item is to be completed where washing machine is cur washer/dryer unit. Price should also include properly terminal	rior of the exhau o framing. rrently located IF	st duct. Se	eal all s	eams in the	syster	n with duct mastic
		Bld Cost:		x	(_=	350
			Base		Quantity		Total Cost
n//a Dr	Dryer Circuit	•			KITCHEN	1	
	Install 220 volt, 30 amp, surface mounted receptacle on an inc	dividual circuit. F	lepair all w	all tear	out required		
		Bid Cost:	*NESSEE AND ASSESSED ASSESSEDA	х	1	=	400 -
بسر		-	Base		Quantity		Total Cost
41)	Oven Circuit		•		KITCHEN	J	
レジー	install 220 volt, 40 amp, surface mounted receptacle on an inc	dividual circuit. R	epair all w	all tear			
	, , , , , , , , , , , , , , , , , , , ,	The second secon	WII 441		i		

Total Cost

Quantity



	119
(7/1/
·	

Electric Tabletop Water Heater

KITCHEN

Install a 38-gallon electric tabletop water heater. Unit shall be insulated, have a glass-lined tank and temperature and pressure relief valve. Water heater shall have a 6-year warranty.



Bid Cost: X = /200 - Base Quantity Total Cost

(49)

Prep & Paint Ceiling

LIVING ROOM

Remove or cover hardware and accessories not to be painted. Scrape loose, peeling, cracked, and blistered areas. Clean oil, grease, fungus, dirt, and dust from surfaces. Fill holes and cracks. Prime all new materials and spot prime existing with acrylic latex. Top coat with Owner's choice of low VOC acrylic flat latex in all habitable rooms and low VOC acrylic semi-gloss latex in kitchen and baths. Replace or uncover hardware, fixtures and accessories. Any moving of furniture required shall be included.



Bid Cost: X = 150 Total Cost

(50)

Resilient Flooring - Vinyl Plank

LIVING ROOM

Install 25 year warrantied resilient plank floor covering per manufacturer's specifications. Include transitions and painted or stained wood quarter-round at all perimeters to complete installation.



Bld Cost: X = 800 - Base Quantity Total Cost

Certification

Contractor Name:

Total Cost

37.700

Signature:

John V. Lyons, S.

Date:

10-4-



TLC by CLT

CITY OF CHARLOTTE
HOUSING & NEIGHBORHOOD SERVICES

Addendum 1 Invitation to Bid HNS 19-21

Documents included in Package:

- 1) Instruction to Bidders
- 2) Specs by Location/Trade (Scope of Work)
- 3) Subcontractor Certifications (if applicable)
- 4) Floor Plan / Site Drawing (if applicable)

Bid Walk & Bid Opening:

Project Address:					
1805 Kennes	aw Dr	Targeted Rehabilitation - Lincoln Heights Neighborhood			
Bid Walk:	9/27/18 at 10:00 am (THURSDAY)				
Bid Opening:	· · · · · · · · · · · · · · · · · · ·				
Client Name: Peggy Covington – Kennesaw		Lead-and rehab only 85			
Project Manager: Elizabeth Lamy Contact Number: 704-620-9090		Contact Number: 704-620-9090			

Bid Walk and Bidding Instructions:

All bid walks are mandatory.

If you are going to be late the policy is the following:

Contact me BEFORE the start time if you are going to be late. If you are going to be more than 10 minutes late, we will proceed without you and you will not be permitted to bid. The day of a bid walk the best way to reach me is at <u>Elizabeth Lamy</u> (cell # 704-620-9090).

Bids must be received by the date, time and place specified. All others will be considered non responsive and disqualified.

The Bids will be opened at 600 East Trade St. immediately following the above due date and time.